

Scottish Church College

1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC / 10/2021-22 Dated 08-02-2022

Contact: Shibnath Bhattacharyya (M -9836272199)

Appropriate quotations are invited in sealed cover from eligible bidder's /suppliers/ vendors for making of road in front of Main Building at Premises no-3 according to the following specification.

Item

Sl.No	Description of item	Unit	Qty	Rate	Amount(Rs)
A	<u>Front damaged Tar road area :</u>				
1.0	Raking out the damaged/eroded tar road with necessary earth work, to expose the hard bed on which concrete to be laid.	Sqm	284.00		
2.0	Single layer Brick on edge for edging to the one side (towards Senatus Secretary office) of road in proper level and alignment including all.	Rmt	24.60		
3.0	One coats Chemical work, (Aquatic bonding polymer agent, Cement, water mixing), application by brush. (For better bonding of new concrete).	Sqm	284.00		
4.0	Existing two numbers pit level up before concreting. By new brick work & necessary concrete.	Nos	2.00		
5.0	Providing and fixing three numbers yard gully pit with heavy cover (400 x 400) mm and necessary fittings complete. (One number yard gully required 3.00 metre 150 mm PVC drainage pipe with cutting the existing soil etc).(others two numbers required necessary 150 mm PVC drainage pipe).	Nos	3.00		
6.0	Providing and fixing one number new Pit, (500 x 500) mm dept as necessary, with 20.0 metre 150 mm PVC drainage pipe with cutting the existing soil etc), (Cover will be heavy duty minimum 6.0 ton capacity)	Nos	1.00		



7.0	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. Dia- 8 mm.(Shell /TaTa), (steel binding 150 cc with proper cheair (Strictly check by engineer in charge).	K.g	1604.80		
8.0	Controlled Cement concrete with well graded stone chips (20 mm nominal size) excluding shuttering and reinforcement with complete design, In ground floor, M 20 Grade.(with necessary special concrete, for high compressive strength).use Aqua tech WRP,(Akzonoble). (1:1.5:3) avg 150 mm thick. (Strictly check thickness by engineer in charge).	Cum	43.00		
9.0	Cutting movement joints in concreting finish with Bitumin seal.	Rmt	32.00		
B	<u>Making new drain periphery wall side at Science annex building.</u>				
1.0	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m.	Cum	4.00		
2.0	Rubbish filling and dressing work complete.	Sqm	12.00		
3.0	Single Brick Flat Soling of picked jhama bricks I dressing bed to proper level and filling joints with local sandncluding ramming.	Sqm	6.00		
4.0	PCC work with curring complete.	Cum	0.50		
5.0	Ist class Brick work with cement, sand mortar, (1:4)	Sqm	12.42		
6.0	Plaster (to wall, floor, ceiling etc.) with sand and including rounding off or chamfering corners as directed and cement mortar.	Sqm	20.00		
7.0	Net cement work with curing work complete.	Sqm	20.00		
C	<u>Repair work old existing drain periphery wall side at Science annex building & damaged area.</u>				
1.0	Carefully Deplastering/ Removal of un serviceable Plaster from wall, per direction of the Consultant.	Sqm	50.00		
2.0	PCC work with curring complete.	Cum	0.40		



3.0	Plaster (to wall, floor, ceiling etc.) with sand and including rounding off or chamfering corners as directed and cement mortar.	Sqm	50.00		
4.0	Net cement work with curing work complete.	Sqm	50.00		
5.0	Removal of debris/garbage collected through work and disposal the same beyond the compound in conformity with the municipal/corporation rule. Including leading to truck and cleaning site in all respect, as directed.	Cum	16.80		
Total amount					
Rs:					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day (Monday to Saturday) between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 09/02/2022 & close on 16/02/2022. The Selection /opening will be made at the Principal's office at 11:00 a.m. on 17/ 02/2022.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal 9/2/22
Principal

Principal
Scottish Church College
Kolkata

