

2

**Scottish Church College**  
**1 & 3 Urquhart Square Kolkata -700 006**

**Notice for quotation**

Ref: Tender Estate/SCC /02 /2023-24 Dated 12-04-2023

Contact: Shibnath Bhattacharyya (M-98362 72199)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for urgent repair with refurbishment to inner portion of Assembly Hall and surroundings according to the following specifications:

| Sl. No | Description of Items  | Unit   | Quantity | Rate | Amount (Rs. ) |
|--------|---|--------|----------|------|---------------|
| 1      | Preparing temporary scaffolding work with Bamboo and rope with necessary platform etc.  | Sq.mt. | 947.76   |      |               |
| 2      | Making temporary scaffolding with steel props steel pipes and rafter staging with working platform ( for removal /refitting) existing all damages ( inside work of the building part by part and steel scaffolding must be used with steel pipes, jack, base plate, M.S. clamp and M.S. pipe etc.)  | Sq.mt. | 376.20   |      |               |
| 3      | Carefully splicing work ( at damaged bearing area of existing ISMB /wooden beam ) with extra steel props support system, providing and fixing new ISMB or ISMC cutting as per requirement wall area with zinc chrome base painting work complete after cutting wall with placing the ISMB or ISMC and welding M.S. plate 6 MM thick as necessary at damaged portion of Existing RSJ/ISMB bearing area with placing concrete bed to the bottom of new ISMB or ISMC at ground floor, including cost of Materials etc. | Unit   | 10 nos   |      |               |
| 4      | Carefully deplastering / removal of damaged and saline effected plaster with cleaning brick/tile joints from old mortar with brush and chisel rods including cleaning debris etc from   | Sq.mt. | 171.75   |      |               |



|    |  |           |            |  |  |
|----|--|-----------|------------|--|--|
|    | walls and ceiling  |           |            |  |  |
| 5  | Repair to cracks on wall through sticking process after deplastering in a width 10cm to 15 cm through underpinning process with necessary grouting , pointing etc through lime , sand mortar ( 1:2)  | Rmt       | 9.75       |  |  |
| 6  | Replastering with lime/sand mortar ( 1:3) in 20 M.M. to 25 M.M thick mixing with water proofing compound with curing complete  | Sq. mt    | 101.75     |  |  |
| 7  | Replastering to ceiling area with lime and sand (1:1) in 5 M.M. to 10 M.M. thick mixing with traditional materials including curing etc.   | Sq. mtrs  | 70.00      |  |  |
| 8  | Carefully examining the existing pillar base inside the Assembly Hall, where cracks has been noticed in seven pillars after raking out the floor tiles with proper strengthening the base, grouting etc. with taking steps on spots including all and finishing etc. with shifting materials . | One item  | Whole job  |  |  |
| 9  | Carefully examining the horizontal beam on pillars, where cracks has been detected with necessary cutting , strengthening and finishing  | One item  | Whole job  |  |  |
| 10 | Scraping and cleaning of Moss, blister and old painted flanked area from the interior parts of hall , corridor carefully through scrapper, sand paper etc. ( lime surface)   | Sq. Mtr.  | 715.57     |  |  |
| 11 | Two coats lime wash with best quality lime, mixing with D.D.L/ Glue with smoothening surface for wall and ceiling  | Sq. Mtrs. | 715.57     |  |  |
| 12 | Three coats lime wash with best quality lime , mixing with D.D.L. /glue with smoothening surface ( only for newly plastered area)for wall and ceiling  | Sq. mtrs  | 171.75     |  |  |
| 13 | Provision for repairing the wooden frame work to sky – light portion to top of roof  | One item  | Whole job  |  |  |
| 14 | Provision for water tightening to the glass joint  | One item  | Whole Job- |  |  |



|    |  |          |           |  |  |
|----|--|----------|-----------|--|--|
|    | through puddling to the sky-light of hall after raking out the old and damaged puddling with great care  |          |           |  |  |
| 15 | Provision for shed with blue zindal tin sheet to all around the sky light to prevent entry of rain water through joints, including M.S. frame work with Epoxy base painting  | Sq. mtrs | 33.00     |  |  |
| 16 | Painting to wooden frame work with two coats of synthetic enamel paint over one coat of primer including finishing after preparing base etc.   | One item | Whole job |  |  |
| 17 | Carefully removing the existing damaged tarfelt from the roof surface, used as water-tightening purpose, after proper examining  | Sq.mtrs  | 145       |  |  |
| 18 | Carefully repair to roof cracks, if any, after removing damaged tarfelt by cutting V-grooves with cutter machine ( 20 to 30 MM depth with 40 to 50 MM width ) as per site condition , cleaning , sealing with lime concrete with lime , surki and brick zira (1:1:2) mixing with traditional materials, cutting etc. | Rmt      | 15        |  |  |
| 19 | Laying new tarfelt to the raked out area with necessary process and cleaning the base with necessary lapping in proper way and finishing with the adjacent area with examining the existing outlets  | Sq. mtrs | 145       |  |  |
| 20 | Carefully two coats primer work with Bituminous tar product to the existing tarfelt joints over roof to prevent any leakage after cleaning dust and dirt etc.  | Sq.mtrs  | 576.70    |  |  |
| 21 | Providing and applying two coats synthetic glossy enamel paint to the inside wall of assembly hall and corridor , as existing and suggested after cleaning and washing the area from dust and oily patches . (ICI/Berger)  | Sq. mtrs | 320.62    |  |  |
| 22 | Provision for cleaning and washing the doors and wooden walling with soap  | Sq. mtrs | 306.51    |  |  |



|       |  |          |           |  |  |
|-------|--|----------|-----------|--|--|
|       | water with due care and drying the same by using cloth.  |          |           |  |  |
| 23    | Provision from painting to the doors and wooden walling with selected synthetic enamel paint in two coats with finishing complete  | Sq. mtrs | 306.51    |  |  |
| 24    | Revival of electric line with necessary casing, wire and fitting etc. including all , if any damaged during raking out plastering  | One item | Whole job |  |  |
| 25    | Carefully cleaning the R.S.J. at ceiling with emery cloth & painting the same with two coats enamel paint including all.   | Sq. mtrs | 365.21    |  |  |
| 26    | Removal of debris from the working site and disposal the same beyond the compound by maintaining Municipal/ Corporation rules.   | One item | Whole Job |  |  |
| 27    | Provision for fixing Aluminium netting in out side ( 38 MM X 38 MM ) with sliding frostrated glass pane window ( in Aluminium frame work ) with dismantling the old windows to prevent pigeon entry. | Sq.mtrs  | 2.16      |  |  |
| Total |  |          |           |  |  |

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **13/04/23** & close on **24 /04/2023**. The Selection /opening will be made at the Principal's office at **2.30 P.M.** on **25/04/2023**.

The Authority of the College reserves the right / discretion for selection based on amount, quality of the bid & bidder.

*Madhumajari Mandal*  
Dr. Madhumajari Mandal  
Principal  
Principal  
Scottish Church College  
Kolkata

*12/4/23*