

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /03 /2023-24 Dated 12-04-2023

Contact: Shibnath Bhattacharyya (M-98362 72199)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for structural repair with refurbishment to staff quarter (Premises No-3) within college campus of the following specifications:


Sl. No	Description of Items	Unit	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with Bamboo and rope with necessary platform etc.	Sq.mt.	1118.5		
2	Making temporary scaffolding with steel props steel pipes and rafter staging with working platform (for removal /refitting) existing all damages (inside work of the building part by part and steel scaffolding must be used with steel pipes, jack, base plate, M.S. clamp and M.S. pipe etc.)	Sq.mt.	45		
3	Carefully dismantling all type of Masonry including cement concrete plain or reinforced, including cleaning debris	Cumt	4.50		
4	Cement concrete avg - 60M.M thick with cement, sand, stone aggregate with polymer mixing including caring	Cumt	4.50		
5	Raking out damaged ceiling of hanging verandah (north) with great care with examining the total by beating if damaged in other places, which were not exposed with cleaning debris	sqmt	11.25		
6	Provision for cleaning the rust from the exposed reinforcement, applying red lead, with adding reinforced through welding process , if any , with necessary lapping including all.	One Item	Whole job		
7	Second concrete work , avg 25 mm to 30 mm thick with cement , sand and fine aggregate with mixing	Sqmt	11.25		



	polymer including curing complete .				
8	Carefully deplastering /removal of damaged and saline effected plaster with cleaning brick/ tile joints from old Morter with brush and chisel rods including cleaning debris etc from walls and ceiling .	Sqmt	417.55		
9	Replastering with lime / sand mortar (1:3) in 20 mm to 25mm thick mixing with water proofing compound with curing complete	Sqmt	417.55		
10	Preparing bead through plaster (1:3) lime and sand as per existing clue available at site to the exterior wall of quarter	Sqmt	16		
11	Scraping and cleaning of moss , blisters and old painted flanked area from the interior parts of hall , corridor carefully through scrapper , sand paper etc. (lime surface)	Sqmt	954.12		
12	two coats lime wash with best quality lime , mixing with D.D.L. /glue with smoothening surface	Sq. mtrs	1039.17		
13	Providing and applying one coat primer of 10% antifungal solution modified high bond , Anti alkalime, anti efforenees sealer Dulax sealer E100+Aquatech PTC or equivalent (Dilution with water in the ratio of (1:1) , ICI /Berger	Sqmt	332.50		
14	Providing applying two coats weather Emulsion Exterior painting work with smoothening the surface ICI/Berger (weather shield)	Sqmt	332.5		
15	Providing and placing of wood bargah (75x65) M.M. with max length 1.30 mt. , cutting nose and carefully removing the old damaged bargahs (Siliguri Sal) including painting work complete	each	50		
16	Providing , fitting and fixing of earthen clay tiles in single layer after raking out the old damaged one with the help of lime , surki and (1:1:1) with sealing the joints (tiles size :450x300xx25x to 30mm	Each	100		



	approximately)				
17	Provision for dismantling the existing damaged /sagged shed from the verandah roof with cleaning debris etc.	Sqmt	67.50		
18	Provision for new shed with zindal blue tin sheet over the varandah including M.S.frame work with Eposy Base painting	Sqmt	67.50		
19	Provision for repairing partly damaged doors and windows to ground floor of quarter with necessary fittings and fixing complete.	One item	Window 20m door - 25 m different size		
20	Providing and painting two coats synthetic enamel paint to old doors and windows after preparing base painting from dust, dirt, and oily patch.	Sq.mtrs	114.12		
21	Providing and painting two coats synthetic enamel paint over one coat of Primer to the newly fixed wooden bargah with smoothening surface etc.	Sqmtr	10		
22	Replacing damaged C.I. pipe as water out let through P.V.C. pipe including , fitting, fixing complete.	One item	Whole job		
23	Revival of electric line damaged during deplastering to the rooms & other places including cost of wire , casing, switch with necessary fittings	One item	Whole job		
24	Repairing the varandah railing with necessary M.S. bar and other fittings etc to prevent any accident	One item	Whole job		
25	Carefully two coats primering with Bituminous tar product and other fittings etc to prevent any accident	Sq. mt	213.75		
26	Carefully cleaning the C.I. members at ceiling of varandah and other iron members at railing , window with emery cloth & painting the same with two coats enamel paint including all.	One item	Whole Job		
27	Repairing and examining the open drain for easy drainage of rain and usable water with necessary brick work, concrete & plaster as per requirement	One item	Whole Job		
28	Stretching of water line from college roof to toilet (north side) through P.V.C. pipe	One item	Whole Job		



	with necessary fittings including all				
29	Removal of debris from the work site and disposal the same beyond the compound by maintaining Municipal /Corporation rules	One item	Whole Job		
Total					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **13/04/23** & close on **24/04/2023**. The Selection /opening will be made at the Principal's office at 3:30 P.M. on **25/04/2023**

The Authority of the College reserves the right / discretion for selection based , amount, quality of the bid & bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal
Principal
Principal
Scottish Church College
Kolkata

12/4/23

