

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tendering Estate/SCC/10/2023-24 Dated 18-05-2023

Contact: Dr. Satadal Bhattacharyya (Mobile- 94334 82779)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for Civil Work at Wann Hostel according to the following specifications:

Repairing work of WANN HOSTEL and STAFF QUATERS of Scottish church college of Kolkata:-

Item No.	Description of Items	Unit	Qty	Rate	Amount	Remarks
1	Preparing temporary scaffolding work with Bamboo and rope with necessary platform etc.	Sqmt	650.10			
2	Carefully dismantling all types of Masonary including cement concrete Plain or reinforced,including cleaning debris.	Cumt	2.42			
3	Carefully deplastering/Removal of damaged and saline effected plaster with cleaning Brick/tile joints from old Morter with brush and chisel rods including cleaning debris etc from workspot.	Sqmt	155.38			
4	Replastering with lime/sand mortar (1:3)in 20M.M to 25M.M thick mixing with water proofing compound with curing complete.	Sqmt	155.38			
5	Brick work with in cement mortar(1:4) in ground floor. (With avaiable brick at site)	Cum	2.42			
6	Plaster (to wall,floor,ceiling etc)with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating,nosing and drip course,scaffolding/staging where necessary (Ground floor)excluding cost of chipping over concrete surface.	Sqmt	22.23			
7	Earth work in excavation of foundation trenches or drains,in all sorts of soil(including mixed soil but excluding later items or sandstone)including removing,spreading or stacking the spoils within a lead of 75m as directed. The item includes necessary trimming the sides of trenches,levelling,dressing and ramming the bottom,bailing out water as required complete.	Cum	4.14			
8	Provision for laying sand in an average thickness of 5cm for levelling purpose.	Cum	1.38			
9	Ordinary cement concrete (mix 1:2:4)with collected brick (20 MM normal size)excluding shuttering and reinforcement,if any,in ground floor (with Preparing brick khoa with avaiable brick).	Cum	2.76			
10	Single layer brick flat soling over sand bed with the avaiable bricks at site.	Sqmt	27.60			



11	Scraping and cleaning of Moss,blisters and old painted flaked area from the interior parts of Rooms Exterior work with due case.	Sqmt	789.79			
12	Two coats lime wash with best quality lime,mixing with D.D.L/glue with smoothening surface to the interior walls.	Sqmt	501.24			
13	Providing and applying two coats weather Emulsion Exterior painting work with smoothening the surface ICI/Berger (weather-shield)	Sqmt	279			
14.a)	P.O.P work with smoothening the surface (wall putty)(Two Coats coating).	Sqmt	55.63			
14.b)	Providing and applying one coat Acrylic Primer and two coats interior Acrylic base painting work,with smoothening the surface (ICI/Berger).	Sqmt	386.43			
15	Provision for stitching work to the cracked wall at west side room with necessary grouting,plastering etc.	One item	Whole job			
16	Provision for folded Aluminium doors/windows with frostrated glass pane including fitting and fixing complete (Top and Bottom portion will be laminated ply and Middle portion will be sliding with outside netting in totally Aluminium frame work).	Sqmt	14			
17	Repairing doors and windows with necessary fittings and fixing including painting.	One item	-do-			
18	Carefully two coats primering With Bituminous tar product,applying over the Existing Tarbelt over roof after cleaning dust & dirt	Sqmt	173.80			
- 2 -						
19	Provision for dismantling the existing old damaged Corrugated sheet from the shade with cleaning debris etc.(only sheet)	Sqmt	82			
20	Provision for changing the damaged M.S angle of existing shade of staff Quarter-including cutting,welding,Eposy painting before fixing the new sheet.	One item	-do-			
21	Provision for painting the M.S /wooden frame work of Existing shade with enamel paint after cleaning rust and preparing base.	One item	-do-			
22	Provision for new shed with zindal blue tin sheet over the existing frame work with Eposy base painting.	Sqmt	82			
23	Provision for installation of pump and overhead water tank with necessary accessories/stretching pipe line with necessary plumbing work for excess supply of water for students and staffs(including all).	One item	Whole job			
24	Examining the roof out let of Hostel and staff Quarter with necessary repairing/grouting,water tightening at junction if necessary.	One item	-do-			
25	Cleaning/Removal of debris from work spot and disposal the same beyond compound by maintaining Municipal/Corporation rules,including all.	One item	-do-			
				Total		

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata - 700 006, on prescribed working day between 10:00 A.M. and 4:00 P.M. The bid / tender may be submitted from 18/05/2023 & close on 27/05/2023. The Selection /opening will be made at the Principal's office at 3:30 P.M. on 29/05/2023.

The Authority of the College reserves the right / discretion for selection based, amount, quality of the bid and bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal
Principal

Principal
Scottish Church College
Kolkata-700 006

18/5/23

