

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /17/2023-24 Dated 28-11-2023

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for the work for wooden glass cabinet/notice board with necessary shed besides the open area of B.Ed Building (Premises no-1) for department of Teachers' Education with the following specifications:

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Scaffolding with short height through bamboo with necessary platform	Sq.mtr.	64.40		
2	Carefully deplastering /Removal of damaged and saline effected plaster with cleaning Brick joints from old mortar with brush and chisel rods including cleaning debris	Sq.mtrs	35.25		
3	Replastering with cement mortar (1:3) in 20mm to 25mm thick mixing with water proofing compound with curing complete	Sq.mtr.	35.25		
4	Scraping and cleaning moss, blisters from the old painting flaked area of walls carefullythrough scrapper, sand paper etc.	Sq.mtrs	35.25		
5	Providing new shade through M.S. square pipe of 50 mm x 50 mm and 50mm x 25mm frame work and 75mm x 75mm vertical post , on which frame work will rest (06 nos) with applying one coat primer and two coats enamel painting with fixing /laying Jindal blue sheet with self tapping screw and finally fixing rain water pipe (4"-0") in supreme brand for easy drainage .	Sq. mtrs	70.50		
6	Providing and applying one coat primer with two coats weather coats painting work including finishing. (ICI/Berger)	Sq.mtrs	70.50		
7	<u>Underground drainage work for developing the area to prevent any type of incident easy movement</u> (a) earth cutting for under ground pipe laying in 30 cm width and 30 cm depth including cutting debris cleaning etc.	Mt	23.00		



	(a) Laying 4" UPVC supreme pipe in proper gradient over one layer brick flat soling on sand bed with silver sand packing /filling to both side of pipe and 2" on the pipe and side of pipe and finally 3" P.C.C. work complete of the drain to bring ground level.	Mt.	23.00		
	(b) Construction of new pit (0.60 x 0.60 x 0.45) with necessary brick work, plaster with neat cement in proper interval for easy cleaning also easy drain out of roof top water necessary M.S. cops.	MT each	3		
8	Repair the main pit and surrounding with cleaning the sludge for easy drain out of water	One Item	Whole Job		
9	Preparation of Notice Board / Wooden glass cabinet (Sample may be seen in college campus) with 3/4" wooden plank at front and soft board at back with clear sliding glass on Aluminium Channel with fixing & fitting on wall surface in proper plumb with lighting arrangement including all size (9'-0" x 3'-0")	Each	7 pcs		
10	Flooring with non-skid / mat finish ceramic tiles (12" x 12") with proper level on cement /sand bed (1:4) with in pointing the tile joints matching to tile joints to the including finishing after chipping out the existing base etc.	Sq. Mtrs	70.50		
				Total	

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **28/11/23** & close on **06/12/23**. The Selection /opening will be made at the Principal's office at **3:00 P.M.** on **07/12/23**

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhuranjari Mendel
Dr. Madhuranjari Mandal
Principal
Principal
Scottish Church College
Kolkata

28/11/23

