

**Scottish Church College**

1 & 3 Urquhart Square Kolkata -700 006

**Notice for quotation**

**Ref: Tender Estate/SCC /08/2026-2027 Dated 16-05-2026**

Contact: Dr. Deepti Myriam Joseph (M- 97486 49433)

Mr. Shibnath Bhattacharyya (M-98362-72199)

Mr. Monojit Mondal ( M- 91230 86001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers for Provision for urgent repair , refurbishment to interior surface and water tightening to terrace d roof with parapet and cornice of residential quarter in the Premises no-2

Sl No.	Description	Unit	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with bamboo and coir rope with necessary platform etc. and dismantling the same after work.	Sq.mtr.	251.11		
2	Carefully deplastering /Removal of damage and saline effected plaster with cleaning brick joints from old mortar with brush and chisel rods including clearing debris ( from interior surface and roof parapet of Building )	Sqmt	189.34		
3	_Replastering with composite mortar (1:1:5) with lime, cement and sand in 20 mm to 25 mm thick mixing with water proofing compound including curing complete.	Sq.mt.	189.34		



4	Raking that the damaged missing and old tiles from the kitchen with chipping the base of the same for fixing new shade of wall tiles	Sq.mtr.	6.90		
5	Fixing and Best quality wall graded tiles ( shade to be selected by Authority) with cement mortar ( 1:6) with pointing the all joints	Sq.mtrs	6.90		
6	Putty work to the repaired area to interior surface of wall and ceiling of toilet including all.	Sq.mtrs	29.31		
7	Painting to the interior surface , where repair attended and ceiling of toilet with one coat primer and two coats DELUX Easy Clean paint after preparing base etc,	Sq.mtr.	29.31		
8	Painting with two coats Delux Easy Clean Paint to the rematching the area of Varandah and Staircase including all.	Sq.ft.	408.21		
9	Raking out the cracked /perforated plaster from the projected cornice with plastering (1:1:5) through composite mortar including scaffolding / replastering ( as per requirement ) in 15 mm to 20 mm thick with clearing debris .	Sq. mtr.	31.66		
10	Water proofing on terraced roof and projected cornice with top of parapet by applying two coats Asian paints small care damp proof liquid after preparing base from dust, dirt and other etc.	Sq.mtr.	591.36		



11	Examining to all the out-lets of terraced roof to find out and damage to fitting or any clearing including replacing and water tightening the same with necessary chemical including necessary scaffolding after proper security with cleaning vegetation from the joint of fitting include all ( including repainting the cornice at South-west corner. )	One Item	Whole Job		
Total					
Tax , if any					
Total after tax					

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **16-05-2026** & closed on **22-05--2026**. The Selection /opening will be made at the College office at **3.00 P.M. on 22-05-2026**

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

*M. Mandel*  
 Dr. Madhumanjari Mandal 16/5/26  
 Principal

Principal  
 Scottish Church College  
 Kolkata

