

Scottish Church College

Kolkata

19th May, 2026

CORRINGENDUM

This is to refer to the Tender No: Tender Estate/SCC /04/2026-2027 Dated 13-05-2026.

That serial numbers 16 to 24 have been added for execution of the work and the submission date is extended to 22.05.2026 before 2.30 pm and the opening date will be 22.05.2026 at 3.00 pm.

Revised Tender is given below :

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Tender Estate/SCC /04/2026-2027 Dated 13-05-2026

Contact: Dr. Deepti Myriam Joseph (M- 97486 49433)

Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 91230 86001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers for Temporary construction (11 ft clear from floor to false ceiling) on the adjoining rooftop of Zoology Staffroom, including the staff room space (2000 sq.ft.) in Scottish Church College the following specifications

Sl No.	Description	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with Bamboo and rope with dressing.	Whole job		
2	Carefully removal of 100 sq .ft. room and others necessary portion and disposal of Rubbish by santraz.	Whole Job		



3	Entire floor (work portion) chipping by santraz and rubbish cleared. By bakwala outside the compound. (20 nos santraz, 20 no. bankwala)	Whole Job		
4	Fire line and earthing line shifted	30 ft. approx		
5	Bathroom renovated { 10'-0" x 8'-0" x 11'-0" (h) } each	Whole Job		
6	Bricks	35,000 pcs		
7	Sand	1,700 cft		
8	Cement	400 bags		
9	Linton shade rod Stone Chips	220 kg 150 cft		
10	Electric point and mainline (200 point) with AC Point (8 nos)	Whole job		
11	UPVC window 4'-0" x 6'-0" (10 pcs)	Whole job		
12	Door wooden 5 pcs (4'-0" x 7'-0")	Whole job		
13	Labour Charge , Rajmistri	Whole job		
14	Plaster, Bricks inside & outside	Whole Job		
15	Pipe line attached with existing line.	Whole Job		
16.	Outside lift structure with ACP finished (4'-0" x 6'-0") Height -40'-0"	Whole job		
17	Lift installed (3 passenger)	Whole job		
18	Iron pipe structure and TATA Tin shed 2000 sqft.	2000 sqft.		
19	Putty finished with labour	40 bags		
20	Outside & inside coloured	100 ltrs		
21	Floor finished with tiles	128 boxes (4'-0' x 2'-0")		



22	PVC false ceiling total rooms and fitting with lights	2000 sqft 100 light (15 watt)		
23	Lifting of total materials	Whole job		
24	Rod Tron Structure 16 ft.	1 pc		
Total				
Tax , if any				
Total after tax				

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 2:30 P.M. The bid / tender may be submitted from **13-05-2026** & closed on **22-05-2026** . The Selection /opening will be made at the College office at **3.00 P.M. on 22-05-2026**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

M. Mendal
Dr. Madhumanjari Mandal
Principal 19/5/26

Principal
Scottish Church College
Kolkata

