

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /23/2026-2027 Dated 05-10-2026

Contact: Dr. Deepti Myriam Joseph (M- 97486 49433)

Mr. Shibnath Bhattacharyya (M-98362-72199)

Mr. Monojit Mondal (M- 91230 86001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers for Urgent Repair with strengthening the M.S. Ceiling members of ceiling, refurbishment to Interior Area with Bituminous Treatment to the Roof Terrace and adjustment of "Seminar Hall "of Scottish Church College, Kolkata of the following specifications;

Sl No.	Description	Unit	Quantity	Rate	Amount (Rs.)
1	Covering the all existing furniture, sound box , A.C. and other types of fitting and fixture after taking due permission from the Authority and if necessary the same should be shifted and fixing in position after execution for prevent any damage.	One item	Whole job	L.S.	
2	Preparing scaffolding work with the help of bamboo and rope with necessary platform for the execution and dismantling the same after execution .	Sq.mtr	231.97		
3	Carefully dismantling the existing damage /swelling false ceiling and stacking the same in a suitable place after taking instruction from Authority , if necessary for re use (including electric fittings)	Sq. mtrs.	130.11		
4	Raking out the damaged /perforated/saline affected plaster from the Interior surface (Over ceiling) from the all sides of wall (after proper examining) with cleaning and cleaning the debris from work spot.	Sq.mtrs	60.89		
5	Replastering work with lime and sand and cement (1:6:1) of composite mortar in 20 mm to 25 mm thick mixing with water proofing compound curing complete .	Sq.mtr	60.89		



6	Carefully examining and attending splicing work at damaged /Rusted bearing area of existing ISMB with extra steel props supported system providing and fixing new ISMB/ISMC cutting as per requirement of wall area with Zincchrome base painting work complete , after cutting wall .with placing ISMB/ISMC and welding M.S.plate 6 mm thick as necessary at damaged portion of existing R.S.J. /I.S.M.B bearing area with placing concrete bed to the bottom of new M.S. I.S.M.B./I.S.M.C including cost of Materials (as per actual requirement)	No	Each piece (10 nos)		
7	Scraping and cleaning the old painted flaked area from the interior walls of " Seminar Hall " below false ceiling through scrapper /sand paper including all.	Sq. mtr	142.27		
8	Painting with silver paint in two coats to the R.S. Joists after preparing base with free from rust of the M.S. Section	Sq.mtr	32.53		
9	Repairing /Replacing the damaged/eroded. clay burnt tiles of ceiling , if any damaged noticed , with necessary repainting works including all as per requirement .	No	Each piece (25 nos)		
10	Painting to the interior surface, overflase ceiling with putty ghola , one coat primer and two coats weather coat painting including all. (Shade of Paint to be selected by Authority)	Sq.mtr	217.10		
11	Painting work to the interior surface , below false ceiling , with putty ghola , one coat primer and two coats " deluxe Easy Clean Paint" including all. (Shade of Paint to be selected by Authority)	Sq. mtrs	115.24		
12	Revival of electric line / Wire , if damaged during execution specially above ceiling , with necessary wire and other fittings / fixtures (including fittings of false ceiling light .) (21 nos – 0.60mt x 0.60 mt)	One Item	Whole Job	L.S.	
13	Fixing and laying false ceiling work Arm strong board (6 mm thick), (0.60 X 0.60) mt. with the help of	Sq. mtr	130.11		



	G.I. / Aluminium frame work in proper way with fixing collected light to ceiling , as it was exist including all.				
14	Provision for cleaning dust and dirt from the roof surface of "Seminar Hall "including adjoining surfaces with liquid Bitumen treatment, maintaining through process (over the exist tarfelting) to give an additional life to the tarfelt (Lump Bitumen to be used after melting) and special attention is to be given to the lap joints of tarfelt, where the same has been loosened . (Work to be attended in the Presence of E.I.C.)	SQ. MTRS	397.30		
15	Cleaning and washing the floor including the different furniture free from any dust and dirt including all. j	One item	Whole Job		
Total					
Tax , if any					
Total after tax					

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **05-10-2026** & closed **11-10-2026**. The Selection /opening will be made at the College office at **3.00 P.M.** on **12-10-2026**

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

M. Mandel

Dr. Madhumanjari Mandal
Principal

5/10/26

Principal
Scottish Church College
Kolkata

