

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /25/2026-2027 Dated 08-10-2026

Contact: Dr. Deepti Myriam Joseph (M- 97486 49433)

Mr. Shibnath Bhattacharyya (M-98362-72199)

Mr. Monojit Mondal (M- 91230 86001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers for fire system work at Pre-1 of Scottish Church College, Kolkata of the following specifications;

No	Item Descriptions	UOM	Qty	Rate	Amount	Supply Rate	Supply Amount	Install Rate	Install Amount	Total Rate	Total Amount	OFFERED MAKE
A	Fire Hydrant System:											
1	Suppling, testing & commissioning of 'B' Class Medium duty MS pipe conforming to IS : 1239/3589 including welding, fittings like elbows, tees, flanges, tapers, nuts, bolts, gaskets etc. and fixing the pipe on the wall/ ceiling with suitable clamp /support frame and painting with two coat or more coats of synthetic enamel paint of required shade complete as required											
(a)	100 mm dia.	Rmt.	12									Jindal
(b)	80 mm dia.	Rmt.	12									Jindal
2	2-Way Fire Brigade Connector having SS NRV's with BFV - 80 mm dia.	Nos.	1									Kartar
3	Monoblock Pump Discharge 54 Cu-m/hr, Head-26 MWC, Power KW-9.3 Make KBL KDS 1348	No.	4									Kirloskar / Lubi
4	Starter panel for Booster Pump (with provision for Changeover switch for building Generator.	No.	2									SAM
5	100 NB dia , Non rising spindle type Gate Valve PN-1.6, IS-14846	No.	5									Kartar
6	100 NB dia Reflux Type, NRV, PN 1.6	No.	4									Kartar



7	100 NB Foot Valve	No.	1										Kirloskar
8	Spring Loaded Air Release Valve of 25 mm. dia	Nos.	2										Zoloto
9	Isolation Ball Valve 1 inch dia	Nos.	2										Zoloto
10	100 MM dial sized pressure Gauge bourdon type (0 to 10 Kgf) with Ø15 MM Isolation Ball Valve	Nos.	6										H Guru
11	3.5C X 16 mm ² Al-Arm Cable	Rmt.	200										Polycab
12	25 x 6 mm GI Strip (Double Run)	Rmt.	50										
13	Providing & Laying of 100 mm. SWR Pipes (For Road Crossing) for laying the pipes of UPVC for OHT filling with all fitting etc. including excavation Back filling complete	Rmt.	0										Supreme
14	Supply, installation, testing & commissioning of PVC Tank of 17000 (15000+2000) litres capacity with all fitting accessories on the top of Pump room roof slab.	Unit	1										Sintex / Patton
15	SF 65 mm dia UPVC Pipe for filling OH Reservoir for both BED Millenium Bldg. with bends , tees etc. complete	Rmt.	120										Supreme
16	SF 75 mm dia UPVC Pipe for filling OH Reservoir for both BED Millenium Bldg. with bends , tees etc. complete	Rmt.	6										Supreme
17	Structural Support for resting 15000 Litre Capacity Overhead Water Tank.	Kg	2400										Jaiswal
18	Scaffolding and dismantling the same after execution of above job.	Job	1										
19	De-erection of existing Pump and	Job	1										



