Scottish Church College

1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /26/2026-2027 Dated 04-11-2026

Contact: Dr. Deepti Myriam Joseph (M- 97486 49433)

Mr. Shibnath Bhattacharyya (M-98362-72199)
Mr. Monojit Mondal (M- 91230 86001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers for Repair work at Department of Chemistry (Science Building) of Scottish Church College, Kolkata of the following specifications;

Sl No.		Description	Unit	Quantity	Rate	Amount (Rs.)
LAB-3						
1		L.P.G. gas distribution system for Chemistry Laboratory				
	A	LPG Gas line It is made of heavy duty TATA G.L. pipe and all ISI marked. Including all fittings, fixing, materials labour charges.	Rft.	**190**		
	b	Pressure Gauge System In Pass Inorganic Chemistry Laboratory Total pressure gauge system by ISI marked fitting high pressure to low pressure connection valve. Including all fittings, fixing, material and labour charges	Unit	1		
	C	Ball valve Heavy duty gun metal casting fitted on each table for safety purpose. Including all fittings, fixing, materials and labour charges.	Each	3		
	D	Gas Cock Heavy duty brass casting chromium plated with acid alkali proof PVC coating straight One way gas cock for	Each	18		

SCOTTISH CHURCH COLLEGE KOLKATA-6

		LPG use. Including all fittings, fixing, materials and labour.				
	E	Bunsen Burner Bunsen Burner screw type made of brass chromium plated with heavy duty spray painted base with stopcock for LPG use.	Each	**18**		
	F	Pressure Table Heavy Duty foftorange colour 7mm ID x 15mm OD pressure tube through gas cock to burner	Coil	**18**		
	G	Warter line for Chemistry Laboratory The water line is made by 12mm dia PVC Supreme white pipe and fittings. Water line inside Chemistry lab -1 for 13 sink fitted on 6 working table (Each Table fitted on 4 sink) and another 1 no sink fitted in side for Fume Hood Chamber. Including all fittings, fixing, materials and labour charge Approx. 60 ft.	Cop m	1 unit		
	H	Gate valve 12mm dia made of heavy duty brass casting (Laxmi brand) gate valve fitted under the sink . Including all fittings, fixing, materials and labour charges.	Each	18		
	I	Porcelain sink Paryware brand 450 mm x 300mm x 175 mm porcelain sink with stainless steel sink waste and waste pipe including all fittings, fixing materials and labour charges	Each	18		
	J	Laboratory water tap Heavy duty three way wate tap made of brass casting with acid alkali proof PVC coating ..... Including all	Each	18		

SCOTTISH CHURCH COLLEGE KOLKATA-6

		fittings, fixing , materials and labour charges .				
	K	Drainage system for Liquid waste Waste line is made of 50mm dia thick wall acid and alkali proof PVC pipe. Including all fittings., fixing, materials and labour charge Approx. 150 rft and supplying, fitting, and fixing half round channel with or without outlet as required 600 mm x 100 mm . white vitreous chinaware.	Cop mp	1 unit		
	L	Lab working Table Renovation The present table at first sink, water line, gas line and gallery dismantling. After then table divided in two part and divided table middle gap in between 21" . At present the size of the table 15' long x 4' wide x 3' hight and middle gap 6 " for water line , gas line and drainage system and two gallery fitted on the table top , Size in the Gallery 6' long x 8' wide x 2' hight with two shelves fitted a middle portion . After the renovation of the table actual size 15 long' x 2' wide with 3' hight and the gap between the table 21" and the gallery is divided into two parts, 1 st part will be fixed on the front table and 2 nd part on the back table. Will also put a bottle safety guard on the gallery back side with CP teak wood 2" x 1" moulded bid the gallery will be paint acid alkali proof epoxy primer and finished paint colour smoke grey.	Each	3		
					Total	
LAB-4						

SCOTTISH CHURCH COLLEGE KOLKATA-6

1		L.P.G. gas distribution system for Chemistry Laboratory				
	A	LPG Gas line It is made of heavy duty TATA G.L. pipe and all ISI marked. Including all fittings, fixing, materials labour charges.	Rft.	**100**		
	b	Pressure Gauge System In Pass Inorganic Chemistry Laboratory Total pressure gauge system by ISI marked fitting high pressure to low pressure connection valve. Including all fittings, fixing, material and labour charges	Unit	1		
	C	Ball valve Heavy duty gun metal casting fitted on each table for safety purpose. Including all fittings, fixing, materials and labour charges.	Each	3		
	D	Gas Cock Heavy duty brass casting chromium plated with acid alkali proof PVC coating straight One way gas cock for LPG use. Including all fittings, fixing, materials and labour.	Each	18		
	E	Bunsen Burner Bunsen Burner screw type made of brass chromium plated with heavy duty spray painted base with stopcock for LPG use.	Each	**18**		
	F	Pressure Table Heavy Duty foftorange colour 7mm ID x 15mm OD pressure tube through gas cock to burner	Coil	**18**		
	G	Warter line for Chemistry Laboratory The water line is made by 12mm dia PVC Supreme white pipe and fittings. Water line inside Chemistry	Cop m	1 unit		

SCOTTISH CHURCH COLLEGE KOLKATA

		lab -1 for 13 sink fitted on 6 working table (Each Table fitted on 4 sink) and another 1 no sink fitted in side for Fume Hood Chamber. Including all fittings, fixing, materials and labour charge .... Approx. 60 ft.				
	H	Gate valve 12mm dia made of heavy duty brass casting (Laxmi brand) gate valve fitted under the sink . Including all fittings, fixing, materials and labour charges.	Each	18		
	i	Porcelain sink Paryware brand 450 mm x 300mm x 175 mm porcelain sink with stainless steel sink waste and waste pipe including all fittings, fixing materials and labour charges	Each	18		
	J	Laboratory water tap Heavy duty three way wate tap made of brass casting with acid alkali proof PVC coating ..... Including all fittings, fixing, materials and labour charges.	Each	18		
	K	Drainage system for Liquid waste Waste line is made of 50mm dia thick wall acid and alkali proof PVC pipe. Including all fittings., fixing, materials and labour charge approx. 150 rft. and supplying, fitting, and fixing half round channel with or without outlet as required 600 mm x 100 mm . white vitreous chinaware.	Cop mp	1 unit		
	L	Lab working Table Renovation The present table at firist sink, water line, gas line and gallery dismantling. After then table divided in two part and divided table middle gap in between 21" . At present	Each	3		

SCOTTISH CHURCH COLLEGE KOLKATA-6

		the size of the table 15' long x 4' wide x 3' hight and middle gap 6 " for water line , gas line and drainage system and two gallery fitted on the table top , Size in the Gallary 6' long x 8' wide x 2' hight with two selves fitted a middle portion . After the renovation of the table actual size 15 long' x 2' wide with 3' hight and the gap between the table 21" and the gallery is divided into two parts, 1 st part will be fixed on the front table and 2 nd part on the back table. Will also put a bottle safety guard on the gallery back side with CP teak wood 2" x 1" moulded bid the gallery will be paint acid alkali proof epoxy primer and finished paint colour smoke grey.				
					Total	
LAB-5						
1		L.P.G. gas distribution system for Chemistry Laboratory				
	A	LPG Gas line It is made of heavy duty TATA G.L. pipe and all ISI marked. Including all fittings, fixing, materials labour charges.	Rft.	**75**		
	b	Pressure Gauge System In Pass Inorganic Chemistry Laboratory Total pressure gauge system by ISI marked fitting high pressure to low pressure connection valve. Including all fittings, fixing, material and labour charges	Unit	1		
	C	Ball valve Heavy duty gun metal casting fitted on each table for safety purpose. Including all fittings, fixing, materials and labour charges.	Each	3		
	D	Gas Cock				

SCOTTISH CHURCH COLLEGE KOLKATA-6

		Heavy duty brass casting chromium plated with acid alkali proof PVC coatingstraight One way gas cock for LPG use. Including all fittings, fixing, materials and labour.	Each	12		
	E	Bunsen Burner Bunsen Burner screw type made of brass chromium plated with heavy duty spray painted base with stopcock for LPG use.	Each	**12**		
	F	Pressure Table Heavy Duty foftorange colour 7mm ID x 15mm OD pressure tube through gas cock to burner	Coil	**12**		
	G	Warter line for Chemistry Laboratory The water line is made by 12mm dia PVC Supreme white pipe and fittings. Water line inside Chemistry lab -1 for 13 sink fitted on 6 working table (Each Table fitted on 4 sink) and another 1 no sink fitted in side for Fume Hood Chamber. Including all fittings, fixing, materials and labour charge .... Approx. 60 ft.	Cop m	1 unit		
	H	Gate valve 12mm dia made of heavy duty brass casting (Laxmi brand) gate valve fitted under the sink. Including all fittings, fixing, materials and labour charges.	Each	12		
	i	Porcelain sink Paryware brand 450 mm x 300mm x 175 mm porcelain sink with stainless steel sink waste and waste pipe including all fittings, fixing materials and labour charges	Each	12		
	J	Laboratory water tap				

SCOTTISH CHURCH COLLEGE KOLKATA-6

		Heavy duty three way wate tap made of brass casting with acid alkali proof PVC coating ..... Including all fittings, fixing, materials and labour charges.	Each	12		
	K	Drainage system for Liquid waste Waste line is made of 50mm dia thick wall acid and alkali proof PVC pipe. Including all fittings. Fixing, materials and labour charge approx 150 rft and supplying, fitting, and fixing half round channel with or without outlet as required 600 mm x 100 mm . white vitreous chinaware.150 rft.	Cop mp	1 unit		
	L	Lab working Table Renovation The present table at firist sink, water line, gas line and gallery dismantling. After then table divided in two part and divided table middle gap in between 21" . At present the size of the table 15' long x 4' wide x 3' hight and middle gap 6 " for water line , gas line and drainage system and two gallery fitted on the table top , Size in the Gallary 6' long x 8' wide x 2' hight with two selves fitted a middle portion . After the renovation of the table acual size 15 long' x 2' wide with 3' hight and the gap between the table 21" and the gallery is divided into two parts, 1 st part will be fixed on the front table and 2 nd part on the back table. Will also put a bottle safety guard on the gallery back side with CP teak wood 2" x 1" moulded bid the gallery will be paint acid alkali proof epoxy primer and finished paint colour smoke grey.	Each	3		

SCOTTISH CHURCH COLLEGE
KOLKATA-6

Total	
Total (Lab 3 + 4 + 5)	
Tax , if any	
Total after tax	

This quotation is to be addressed to the Principal, Scottish Church College and has to be submitted to the Principal's office in Scottish Church College, at 1 & 3 Urquhart Square, Kolkata – 700 006, in due prescribed format on working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **4-11-2026** & closed on **12-11-2026**. The Selection /opening will be made at the College office at 3.00 **P.M.** on **13.11.2026.**

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

M. Mandal 4/11/26

Dr. Madhumanjari Mandal
Principal

Principal
Scottish Church College
Kolkata

SCOTTISH CHURCH COLLEGE ★ KOLKATA-6